PROJECT :FARM TO MARKET ROAD (EARTH ROAD-NEW)LOCATION :SUBJECT :BUDGETARY ESTIMATE ONLY (BY CONTRACT)

Project Description:

a.	Earth Road	-	New
b.	Roadway width	-	4.0 m
c.	Thickness	-	0.30 m Common borrow
d.	Length	-	1.0 km

Calendar days to complete – 20 days

Estimated Direct Cost by Items of Work

Scope of work

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	DIRECT UNIT COST	TOTAL DIRECT COST
104 (1)	Borrow materials	1,560	cu.m.	500.00	780,000.00
С					
500	Reinforce Concrete Pipe	35	l.m.	1,793.19	62,761.60
505	Stone masonry for head	10	cu.m.	2,553.86	25,538.60
	wall				
TOTAL					868,300.20

Note: Prices were based on January 2007.

BREAKDOWN OF ESTIMATED EXPENDITURES		% of Total	Amount
I.	Estimated Contract Cost		
	a. Estimated direct cost (EDC)b. Mobilization/Demobilization (1%)		868,300.20 8,683.00
	 Materials 1.1 Supply/Delivery 		
	 2. Labor 2.1 Direct labor 2.2 Leave 2.3 Philhealth 2.4 State Insurance 		
	c. Indirect Cost		
	1. Overhead expenses, contingency Miscellaneous expenses (10-13%)		104,196.02
	2. Profit (10-15%)		121,562.00
	3. VAT (10%)		86,830.02
	Sub-Total	96.68	1,189,571.24
II.	Estimated Government Expenses		
	 ROW/Site Acquisition Soil Exploration Project Management (up to 5% of EDC) 	3.31	40,810,10
		5.51	40,810.10
	Sub-Total		40,810.10
III.	Contingencies/Reserves		
	 Physical (up to 15% of EDC) Price Escalation (up to 12% of EDC) 		
	TOTAL PROJECT COST	100 SAY	1,230,381.34 1,240,000.00